

**DEPARTMENT OF AGRICULTURE
OFFICE OF THE ADDL.DIRECTOR OF AGRICULTURE (H)
BOTANICAL GARDEN- PONDICHERRY**

-:0:0:-
No.5/HORTI/ADA(H) /BG/QUARTERS/2016-17/1159

dated :12.09.2016

To,

(See over leaf)

Sir,

Sub: Horticulture – BG – Laying of edging with brick and laying of foot path with precast tiles for Laying of Lawn at Botanical Garden - calling of quotations – Reg.

-:0:0:-

Kindly offer your lowest rate for carrying out the below mentioned work related to laying of Lawn at Botanical Garden as detailed below.

2. Your quotations in sealed cover super scribed, as "Quotation for edging with brick and laying of foot path with precast tiles for Laying of Lawn at Botanical Garden" should reach this office of the undersigned on or before 23/09/2016.

Sl. No		Quantity	Unit	Rate/unit	Amount(Rs)
	Edging with bricks laid dry length wise including excavation, refilling consolidating with hand packing and spreading neatly surplus earth within a lead of 50m - bricks.50 class designation – FPS	450	Metre		
	Chequered precast concrete tiles 22mm thick in foot path and courtyard jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and cleaning etc. complete on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand). ordinary cement without any pigment.	525	sq mtr		

Terms and conditions:

- Taxes and charges : The rate quoted shall be inclusive of all taxes and surcharges
- Terms of work and supply : The work and supply should be started immediately of placing the orders and the rate quoted should be inclusive of labour, material, etc.,
- Insurance : No insurance charges will be paid by this office.
- Consignee : The Additional Director of Agriculture (H), Botanical Garden, Puducherry.
- Payment : Made through DAT, Puducherry upon receipt of pre receipted bill in duplicate.



ADDL. DIRECTOR OF AGRICULTURE (HORTI),